



राष्ट्रीय प्रौद्योगिकी संस्थान हमीरपुर

हमीरपुर (हि.प्र.) - 177 005 (भारत)

[भारत सरकार शिक्षा मंत्रालय के तहत एक राष्ट्रीय महत्व का संस्थान]

NATIONAL INSTITUTE OF TECHNOLOGY HAMIRPUR

HAMIRPUR (H.P.) - 177 005 (INDIA)

[An Institute of National Importance under Ministry of Education (Shiksha Mantralaya)]

{OFFICE OF CONSTRUCTION CELL}

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the Director, NIT Hamirpur from the various contractor/firms for the work of "Repair of old damaged GI pipeline in one bathroom and water proofing on store terrace in Parvati Girls Hostel and replacement of damaged pipeline near pump house adjacent of Himgiri Hostel at NIT Hamirpur (H.P)". The Quotation must be reached in the office of the undersigned on or before **08/09/2025 up to 03:00 P.M.**, which shall be opened on the same day at **03:30 P.M** in the presence of intending quotationers or their authorized representative who may be present themselves.

Name of Work: Repair of old damaged GI Pipeline in one bathroom and water proofing on store terrace in Parvati Girl Hostel and replacement of damaged GI pipe lines near pump house adjacent to Himgiri Hostel at NIT Hamirpur.

Estimate cost :- 3.64 Lakhs

Time Period for :- 60 Days
completion of work

Sr. No	Description of Item	Qty.	Unit	Rate (In Rs.)	Amount (In Rs.)
1	Dismantling wall tile work in toilets laid in cement mortar including stacking material within 50 meters lead as per direction of Engineer-in-charge. including entire carriage of materials within all leads, lifts, height and cost of all other incidentals. (For thickness of tiles 10 mm to 25 mm)	30	Sqm.		
2	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 meters lead as per direction of Engineer-in-charge. including entire carriage of materials within all leads, lifts, height and cost of all other incidentals (15 mm to 40 mm nominal bore).	50	Mtr.		
3	12 mm cement plaster on the rough side of single or half brick wall of Cement Mortar 1:6.as per direction of Engineer-in-charge. including entire carriage of materials within all leads, lifts, height and cost of all other incidentals.	30	Sqm		
4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes of make Vectus/Prince/Astral/ having thermal stability for hot & cold-water supply and all CPVC plain & brass threaded fittings, including fixing the pipe with ss clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall. as per direction of Engineer-in-charge. including entire carriage of materials within all leads, lifts, height and cost of all other incidentals (20mm nominal dia Pipes).	40	Mtr.		
5	Providing and fixing CPVC Brass Tee 20 mm.	10	Each		
6	Providing and fixing CPVC Brass Elbow 20 mm.	25	Each		

7	Providing and fixing CPVC Socket MTA/ FTA 20 mm.	5	Each		
8	Providing and fixing 1 st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make Kajaria/Nitco/Somany/AGL /Spenzo, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete. including entire carriage of materials within all leads, lifts, height and cost of all other incidentals.	25	Sqm.		
9	Water proofing on Existing Kota Stone Slab by Cleaning of all joints of existing Kota stone and Filling of all Joints with water proof liquid Epoxy Component complete as per direction by the Engineer- in - charge. including entire carriage of materials within all leads, lifts, height and cost of all other incidentals. Note:- Warranty Certificate for Water Proofing for 10 Years may also be Provided by Contractor/Agency.	1550	Sqft.		
10	Earth work in Excavation by Mechanically/Manual Means over area 60 cm in depth, 1.00meter in width including getting out and disposal of excavated earth complete as per direction of Engineer-in-charge.	30	Cum		
11	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level as per direction of Engineer-in-charge. including entire carriage of materials within all leads, lifts, height and cost of all other incidentals. 1:3:6 (1 Cement: 3 coarse sand (zone-III) derived from natural sources: 6 graded stone aggregate 20 mm nominal size derived from natural sources:	2	Cum		
12	Providing and fixing G.I. pipes of make Unik/Jindal threaded or Welded Joints of required dia Complete including trenches/excavation/ refilling as per requirement of site.				
12.1	50 mm dia nominal bore	30	Meter		
12.2	65 mm dia nominal bore	18	Meter		
13	Providing and fixing G.I Elbow 50mm of Unik, Jindal Make	5	Each		
14	Providing and fixing G.I Elbow 65mm of Unik, Jindal Make	5	Each		
15	Providing and fixing G.I Union 50mm of Unik, Jindal Make	4	Each		
16	Providing and fixing G.I Union 65mm of Unik, Jindal Make	4	Each		
17	Providing and fixing Gate Valve 50mm nominal Dia	2	Each		
18	Providing and fixing Gate Valve 65mm of nominal Dia	2	Each		
19	Providing and fixing G.I Socket 50mm	7	Each		
20	Providing and fixing G.I Socket 65mm	7	Each		
21	Providing and fixing G.I Nipple				
21.1	50mm X 300mm	7	Each		
21.2	50mmX 200mm	6	Each		
21.3	50mm X 100mm	6	Each		
21.4	50mm X 50mm	6	Each		
21.5	65mm X 300mm	6	Each		
21.6	65mm X 200mm	6	Each		
21.7	65mm X 100mm	6	Each		
21.8	65mm X 50mm	6	Each		
22	Safeda 250gm	6	Each		

23	Thread	30	Each		
24	Welding on G.I pipe line joints (L.S)	5000	Cm		
Total Amount:-					

TERMS AND CONDITIONS:-

1. Postal Instruction: Quotations addressed to the undersigned may be sent on Letter Head Pad of the firm as per schedule notified in quotations in sealed envelopes super-scribing the items of the offer and the date of opening. Offers/quotations received through electronic mail or fax will not be considered.
2. Validity: Minimum validity of the quotation will be 03 months from the date of opening of the quotation.
3. Price/Rate: The price of the material may be quoted in Indian rupees & inclusive of all taxes as per Govt. of India notification.
4. GST: All the firms may invariably mention their GST numbers on quotation/tender, failing which quotations may not be considered valid. Further, this Institution does not issue any C/D Concessional form, so the GST applicable as per actual rates must be mentioned in the offer. In case GST is not mentioned, the rates shall be treated as inclusive of all taxes.
5. NIQ Opening: The quotation must reach in the office of the undersigned on or before **08/09/2025 at 03:00 P.M.**
6. Right of Acceptance/Rejection: Right of acceptance and rejection of any quotation in part or full without assigning any reason are reserved with the institution authorities.
7. In case of any dispute the jurisdiction of Hamirpur (H.P) Courts shall apply.


 Executive Engineer (Civil)
 Construction Cell
 NIT Hamirpur (HP)

No. NIT/HMR/CC/CB/S-4/ 2025-26/**2188-95**
 Copy to the:-

1. Director for kind information please.
2. Registrar for kind information please.
3. Dean (P&D) for kind information please.
4. Associate Dean (CIM) for kind information please.
5. Faculty In-charge (C.C.) for getting the advertisement displayed on the institute website.
6. Assistant Engineer (Civil) for information please.
7. Drawing Branch of Construction Cell for information please.
8. Notice Board.


 Executive Engineer (Civil)
 Construction Cell
 NIT Hamirpur (HP)

Dated **24/08/2025**