



राष्ट्रीय प्रौद्योगिकी संस्थान हमीरपुर

हमीरपुर (हि.प्र.) - 177 005 (भारत)

[भारत सरकार शिक्षा मंत्रालय के तहत एक राष्ट्रीय महत्व का संस्थान]

NATIONAL INSTITUTE OF TECHNOLOGY HAMIRPUR

HAMIRPUR (H.P.) - 177 005 (INDIA)

[An Institute of National Importance under Ministry of Education (Shiksha Mantralaya)]

{OFFICE OF CONSTRUCTION CELL}

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the Director, NIT Hamirpur from the various contractor/firms for the work of “**Construction of Manholes at various locations in NIT Hamirpur**”. The Quotation must be reached in the office of the undersigned on or before **16/06/2026 up to 03:00 P.M.**, which shall be opened on the same day at **03:30 P.M** in the presence of intending quotationers or their authorized representative who may be present themselves.

Name of Work: Construction of Manholes at various locations in NIT Hamirpur.

Estimate cost :- 4,79,442/-

Time Period for 60 Days

completion of work:-


Sr. No	Description of Item	Qty.	Unit	Rate (In Rs.)	Amount (In Rs.)
1	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design. Inside size 120x90 cm and 90 cm deep including C.I. cover with frame (medium duty) 500 mm internal diameter, total weight of cover and frame to be not less than 116 kg (weight of cover 58 kg and weight of frame 58 kg). With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	12	Each		
2	Extra for depth for manholes Size 120x90 cm With common burnt clay F.P.S. (nonmodular) bricks of class designation 7.5	3	Meter		
3	12 mm cement plaster finished with a floating coat of neat cement of mix 1:3 (1 cement: 3 fine sand)	50	Sqm.		
4	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead up to 50 m and lift up to 1.5 m, as directed by Engineer-in charge. including entire carriage of materials up to leads lifts and heights. All Kind of Soil	40	Cum.		
5	Dismantling of manhole including R.C.C. top slab or C.I. cover with frame, including stacking of useful materials near the site and disposal of unserviceable materials within 50 m lead as per direction of Engineer-in-charge. Rectangular manhole 120x90 cm and 90 cm deep	12	Each		
6	Providing of PVC Pipe 200mm diameter for temporary By-pass of sewage during Construction of manhole with all essential fitting etc.	20	Meter		

H.

7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : including entire carriage of materials up to leads lifts and heights. 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	2	Cum		
8	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in. Cement mortar 1:4 (1 cement : 4 coarse sand)	2.5	Cum		
Amount:-					
GST@					
Total Amount with GST:-					

TERMS AND CONDITIONS:-

1. Postal Instruction: Quotations addressed to the undersigned may be sent on Letter Head Pad of the firm as per schedule notified in quotations in sealed envelopes super-scribing the items of the offer and the date of opening. Offers/quotations received through electronic mail or fax will not be considered.
2. Validity: Minimum validity of the quotation will be 03 months from the date of opening of the quotation.
3. Price/Rate: The price of the material may be quoted in Indian rupees & inclusive of all taxes as per Govt. of India notification.
4. GST: All the firms may invariably mention their GST numbers on quotation/tender, failing which quotations may not be considered valid. Further, this Institution does not issue any C/D Concessional form, so the GST applicable as per actual rates must be mentioned in the offer. In case GST is not mentioned, the rates shall be treated as inclusive of all taxes.
5. NIQ Opening: The quotation must reach in the office of the undersigned on or before **16/06/2026 at 03:00 P.M.**
6. The issue or notice raised by HPSPCB or any other body in regard to any observations during execution of the work shall be sole responsibility of agency/contractor.
7. Time period for completion of work is 60 days after acceptance of work order.
8. Right of Acceptance/Rejection: Right of acceptance and rejection of any quotation in part or full without assigning any reason are reserved with the institution authorities.
9. In case of any dispute the jurisdiction of Hamirpur (H.P) Courts shall apply.



 Executive Engineer (Civil)
 Construction Cell
 NIT Hamirpur (HP)

Dated 05/06/2026

No. NIT/HMR/CC/CB/S-4/ 2025-26/1048-55

Copy to the:-

1. Director for kind information please.
2. Registrar for kind information please.
3. Dean (P&D) for kind information please.
4. Associate Dean (CIM) for kind information please.
5. Faculty In-charge (C.C.) for getting the advertisement displayed on the institute website.
6. Assistant Engineer SG-I for information please.
7. Drawing Branch of Construction Cell for information please.
8. Notice Board.


 Executive Engineer (Civil)
 Construction Cell
 NIT Hamirpur (HP)